

~~OFFICIAL USE~~
~~ONLY~~

5 U.S.C. 552 (b)(2) and (b)(3),
FOIA Exemptions 2 and 3,
apply to this document.



HARDNESS VERIFICATION OF ANTENNA LINE PENETRATIONS

STANDARDS AND TECHNOLOGY INTEGRATION MEETING, *Sanitized Version*

21 SEPTEMBER 1994

W. BEREUTER, L. ROSE, T. ZWOLINSKI, B. HARLACHER

5 U.S.C. 552 (b)(2) and (b)(3),
FOIA Exemptions 2 and 3,
apply to this document.

DISTRIBUTION STATEMENT A:
Approved for Public Release -
Distribution Unlimited

"Test Techniques for Antenna Line Penetrations," 23 May 1994, MRC/COS-R-1394
[REDACTED], 8/22-9/1/94 - Quick Look Data

~~OFFICIAL USE~~
~~ONLY~~

19981106 123

PORTIONS OF DOCUMENT(S) RELEASED
UNDER THE FREEDOM OF INFORMATION ACT
DOWA CASE NO. 47-033

The diagram illustrates the signal path and shielding for a radio system. The components are connected in series from left to right:

- ANTENNA**: Represented by a Y-shaped symbol on the far left.
- LIGHTNING ARRESTOR**: A rectangular block connected to the antenna.
- MATCHING NETWORK**: A rectangular block connected to the lightning arrester.
- BALUN**: A rectangular block connected to the matching network.
- COAX. LINE**: A line connecting the balun to the EBA/filter block.
- EBA / FILTER**: A rectangular block connected to the coaxial line.
- RADIO**: A rectangular block connected to the EBA/filter.
- FACILITY SHIELD**: A thick vertical bar with diagonal hatching, positioned between the EBA/filter and the radio.

Two injection points are indicated by diagonal lines pointing to the main signal path:

- ADDITIONAL INJECTION LOCATION REQUIRED BY MIL-STD-188-125 (SPM) IF LINK IS MEE**: Points to the connection between the lightning arrester and the matching network.
- INJECTION LOCATION SPECIFIED BY MIL-STD-188-125**: Points to the coaxial line between the balun and the EBA/filter.

PROCEDURES REQUIRED BY MIL-STD-188-125

1. The test waveform is a damped sinusoid ($Q=10\pm3$) with peak amplitude and fundamental frequency determined from the maximum linear dimension (L) of the antenna radiating structure by the algorithm:



If $300\text{ m} >$
if $20\text{ m} >$
if

$L > 20\text{ m},$
 $L > 3\text{ m},$
 $L < 3\text{ m},$

then $f_c = 2\text{ MHz},$
then $f_c = 30\text{ MHz},$
then $f_c = 200\text{ MHz},$

$I_{pk} = 2500\text{ A};$
 $I_{pk} = 900\text{ A};$
 $I_{pk} = 250\text{ A}.$

2. The injections must be performed in the acceptance test and verification test configurations.



- Difficulties with implementation of MIL-STD-188-125 requirements
 - No such pulsers available
 - Test waveforms often do not represent HEMP stresses (test waveform may be inadequate in some cases)
 - Acceptance test pass/fail criteria usually cannot be met
- Most antenna line penetrations will be SPMS
- 5-step procedure proposed to test antenna lines as SPMS
- Lab and field tests to demonstrate proposed procedure

PROPOSED TEST PROCEDURE

**STEP 1: VERIFY PROT. EQUIPMENT IS WORKING PER SPECIFICATIONS
(CWDD of FL, voltage step fcn test of ESA)**

STEP 2: DECIDE PCI LOCATION

**STEP 3: ESTIMATE LINEAR HEMP STRESS
(Wide-area CWIL, local CWIL, other)**

STEP 4: SELECT PULSER(s), INJECT, AND ESTIMATE TEST COVERAGE

$$\max I_{RES}^{HEMP} \text{ vs. } \max I_{RES}^{PCI}$$

$$\max I_{DEL}^{HEMP} \text{ vs. } \max I_{DEL}^{PCI}$$

- **HEMP vs. pulse induced outage time (if link is MEE)**

STEP 5: REPEAT STEP 1

EVALUATION OF TEST COVERAGE (ACCEPTANCE TEST CONFIGURATION)

BELOW ESA BREAKDOWN					ABOVE ESA BREAKDOWN				
MAX I _{DEL}		MAX I _{RES} (c)		IS TEST COVERAGE ADEQUATE	MAX I _{DEL} (a)		OUTAGE	MAX I _{RES}	IS TEST COVERAGE ADEQUATE
Peak (A)	RAINT (A-s.5)	Peak (A)	RAINT (A-s.5)		Peak (A)	RAINT (A-s.5)	Time (ns)	Peak (A)	
6.40E1	2.50E-2	5.60E1	2.48E-2	n.a.	2.37E3	9.86E-1	500	(c)	n.a.
5.00E1	3.18E-2	1.65E1	4.30E-3	Maybe	2.50E3	1.68E0	1000	1.75E1	Yes
4.00E1	2.52E-2	2.80E0	8.42E-4	No	2.50E3	1.58E0	>1000	(c)	Yes

HEMP on

E1 Pulser


2MHz DS per
MIL-STD-188-125

TEST OBJECTIVES

1. Implement/demonstrate the proposed test procedures
2. Evaluate the test coverage achieved with charged line pulser
3. Determine feasibility of local CW illumination to estimate HEMP stresses

*Page 9 removed
in its entirety*


Table 2-2. Specifications of the ESA tested.



Model:	Polyphaser IS-B50LN-CO
Type:	Gas Tube
Turn-on Characteristics:	600 VDC + /- 20%
	2.5 ns for 2 kV/ns input

Table 2-1. Specifications of the ~~XXXXXX~~ filters tested.


XXXXXX	XXXXXX	XXXXXX	XXXXXX
XXXXXX	XXXXXX	XXXXXX	XXXXXX



HEMP STRESS ESTIMATES USING WIDE AREA CWIL vs. LOCAL CWIL WITH SE ANTENNAS


Antenna	Port	ESA + K&L FL:	Peak Curr. I_{DEL} (A)		Peak Curr. I_{RES} (A)	
			Wide Area CWIL	Local CWIL	Wide Area CWIL	Local CWIL
[REDACTED]	[REDACTED]	[REDACTED]	59.2 *	76.2	13.4 *	14.8
			54.7	97.1	2.7	1.8
			35.8	76.3	1.5	3.0
			30.2	45.8	4.5	6.3
			43.3	53.2	2.9	4.5

* The site did not permit illumination testing in the HF band, except for these two measurements.




HEMP STRESS EST. METHOD #3: CALC. I_{SC}^{ANT} , $MSD \cdot Z_{ANT}$ - IN PROGRESS


Delivered Current [REDACTED] HF Filter




Residual Current
[REDACTED] HF Filter




Delivered Current
[REDACTED] VHF Filter




Residual Current [REDACTED], VHF Filter




Delivered Current
[REDACTED], UHF Filter




Residual Current
[REDACTED] UHF Filter




Delivered Current
[REDACTED] VHF Filter




Residual Current
[REDACTED] VHF Filter



Delivered Current
[REDACTED] UHF Filter







Verification Test of the [REDACTED] Antenna Penetration

Estimated HEMP Stress: Delivered to the protection device $I_{DEL} : 59.2 \text{ A}$
 Residual on the protected side $I_{RES} : 39.8 \text{ A}$


Pulse current injection with a 5 m long charged line pulser.				
Pulser Charge Voltage (V):	Ant. line terminated in 50 ohms		Ant. line terminated in the radio	
	$I_{DEL} \text{ (A)}$	$I_{RES} \text{ (A)}$	$I_{DEL} \text{ (A)}$	$I_{RES} \text{ (A)}$
270	1.7	0.6		1.9
540	3.8	1.7	4.3	5.1
1300	9.9	4.4	11.8	8.7
2700	20.6	5.8	21.3	
5400	95.5	10.5		
7500	139.0	10.0		
10000	188.0	8.9		




Measured Currents vs. Charge Voltage HF Filter




Delivered Current [REDACTED] HF Filter




Measured Currents vs. Charge Voltage VHF Filter




Delivered Current [REDACTED], VHF Filter




Measured Currents vs. Charge Voltage
 Filter



Delivered Current [REDACTED] Filter



CONCLUSIONS

1. The proposed verification test procedure was implemented and demonstrated at an operational site.
2. The test coverage provided by the charged line pulser was adequate to test the HF, VHF, and UHF antenna lines.
3. HEMP stresses can be adequately estimated with local CW illumination using the SE transmit antennas.
4. The verification test configuration (antenna leg in parallel with the pulser) did not significantly reduce the test coverage.
5. The  operated normally even when the pulser TEE was inserted; i.e., the TEE did not interfere with the link.